



Note: Tremco CPG suggests that all laps in the membrane system be avoided within a 150mm vicinity of the construction joint. This detail is suggested based on the assumption that there is negligible movement or shrinkage of the concrete at this joint. Consult with Tremco CPG for Project Specific advice if this is not the case.



www.tremco.com.au
12/4 Southridge St, Eastern Creek, NSW 2766
Phone : (02) 9638 2755 * Fax: (02) 9638 2955

Project: DualProof C Below Slab-on-Grade
Detail: Slab on Grade - Construction Joint

This detail is intended for conceptual purposes only.

Drawn by: AH

Checked by: XX

Scale: N.T.S

Sheet Number:

Date: 06/06/2025

File Name:
DualProof C - Slab on
Grade - Construction
Joint

Rev #:

05